


Prüfbericht-Nr.: Test report no.:	CN21U8UU 001		Auftrags-Nr.: Order no.:	170259209	Seite 1 von 29 Page 1 of 29
Kunden-Referenz-Nr.: Client Reference No.:	N/A	Auftragsdatum: Order date.:		2020.12.29	
Auftraggeber: Client:	Lumi United Technology Co., Ltd. 8th Floor, JinQi Wisdom Valley, No.1 Tangling Road, Liuxian Ave, Taoyuan Residential District, Nanshan District, Shenzhen, Guangdong, P.R. China				
Prüfgegenstand: Test item:	Smart Wall Switch				
Bezeichnung / Typ-Nr.: Identification / Type No.:	WS-EUK03, WS-EUK04				
Auftrags-Inhalt: Order content:	TÜV Rheinland EMC service				
Prüfgrundlage: Test specification:	EN 60669-1:1999+A1+A2 EN 60669-2-1:2004+A1+A12				
Wareneingangsdatum: Date of sample receipt:	2020.12.31				
Prüfmuster-Nr.: Test sample No.:	A002979252 005				
Prüfzeitraum: Testing period:	Refer to test report				
Ort der Prüfung: Place of testing:	Refer to section 2.1				
Prüflaboratorium: Testing laboratory:	TÜV Rheinland (Guangdong) Ltd.				
Prüfergebnis*: Test result*:	Pass				
geprüft von: tested by:			genehmigt von: authorized by:		
Datum: 2021.03.12 Date:			Datum: 2021.03.18 Date:		
Stellung/Position: Amy Wang/Project Manager			Stellung/Position: Cherry He/TC		
Sonstiges / Other: The RF characteristics of this electronic switch were not evaluated in this report.					
Zustand des Prüfgegenstandes bei Anlieferung: Condition of the test item at delivery:	Prüfmuster vollständig und unbeschädigt Test item complete and undamaged				
* Legende: 1 = sehr gut 2 = gut P(ass) = entspricht o.g. Prüfgrundlage(n)	3 = befriedigend F(ail) = entspricht nicht o.g. Prüfgrundlage(n)			4 = ausreichend N/A = nicht anwendbar	5 = mangelhaft N/T = nicht getestet
Legend: 1 = very good 2 = good P(ass) = passed a.m. test specifications(s)	3 = satisfactory F(ail) = failed a.m. test specifications(s)			4 = sufficient N/A = not applicable	5 = poor N/T = not tested
<p>Dieser Prüfbericht bezieht sich nur auf das o.g. Prüfmuster und darf ohne Genehmigung der Prüfstelle nicht auszugsweise vervielfältigt werden. Dieser Bericht berechtigt nicht zur Verwendung eines Prüfzeichens.</p> <p>This test report only relates to the a. m. test sample. Without permission of the test center this test report is not permitted to be duplicated in extracts. This test report does not entitle to carry any test mark.</p>					

Test Summary

5.1.1 HARMONICS CURRENT EMISSION ON AC MAINS

RESULT: Pass

5.1.2 VOLTAGE CHANGES, VOLTAGE FLUCTUATIONS AND FLICKER

RESULT: Pass

5.1.3 TERMINAL CONTINUOUS DISTURBANCE VOLTAGE

RESULT: Pass

6.2.1 POWER-FREQUENCY MAGNETIC FIELD

RESULT: N/A

6.2.2 RADIO-FREQUENCY COMMON MODE / CONDUCTED SUSCEPTIBILITY (CS)

RESULT: Pass

6.2.3 RADIO-FREQUENCY ELECTROMAGNETIC FIELD SUSCEPTIBILITY (RS)

RESULT: Pass

6.3.1 ELECTRICAL FAST TRANSIENTS (EFT)

RESULT: Pass

6.3.2 SURGE

RESULT: Pass

6.3.3 ELECTROSTATIC DISCHARGES (ESD)

RESULT: Pass

6.4.1 VOLTAGE DIPS AND INTERRUPTIONS

RESULT: Pass

Contents

1	GENERAL REMARKS	5
1.1	COMPLEMENTARY MATERIALS	5
2	TEST SITES.....	5
2.1	TEST FACILITIES.....	5
2.2	LIST OF TEST AND MEASUREMENT INSTRUMENTS.....	5
3	GENERAL PRODUCT INFORMATION	6
3.1	PRODUCT FUNCTION AND INTENDED USE	6
3.2	RATINGS AND SYSTEM DETAILS	6
3.3	INDEPENDENT OPERATION MODES.....	7
3.4	NOISE GENERATING AND NOISE SUPPRESSING PARTS	7
3.5	SUBMITTED DOCUMENTS	7
4	TEST SET-UP AND OPERATION MODES.....	8
4.1	PRINCIPLE OF CONFIGURATION SELECTION.....	8
4.2	TEST OPERATION AND TEST SOFTWARE	8
4.3	SPECIAL ACCESSORIES AND AUXILIARY EQUIPMENT.....	8
4.4	COUNTERMEASURES TO ACHIEVE EMC COMPLIANCE	8
5	TEST RESULTS EMISSION.....	9
5.1	EMISSION IN THE FREQUENCY RANGE UP TO 30 MHz.....	9
5.1.1	Harmonics Current Emission on AC Mains	9
5.1.2	Voltage Changes, Voltage Fluctuations and Flicker	11
5.1.3	Terminal Continuous Disturbance Voltage	13
6	TEST RESULTS IMMUNITY	15
6.1	CLASSIFICATION OF APPARATUS	15
6.2	CONTINUOUS DISTURBANCES	16
6.2.1	Power-frequency Magnetic Field.....	16
6.2.2	Radio-frequency Common Mode / Conducted Susceptibility (CS)	17
6.2.3	Radio-frequency Electromagnetic Field Susceptibility (RS)	19
6.3	TRANSIENT DISTURBANCES.....	21
6.3.1	Electrical Fast Transients (EFT).....	21
6.3.2	Surge	23
6.3.3	Electrostatic Discharges (ESD)	25
6.4	POWER SUPPLY ALTERATION	27
6.4.1	Voltage Dips and Interruptions.....	27
7	LIST OF TABLES	29

Prüfbericht - Nr.: CN21U8UU 001
Test Report No.

Seite 4 von 29
Page 4 of 29

8	LIST OF PHOTOGRAPHS	29
----------	----------------------------------	-----------

1 General Remarks

When applying the basic standards in this test report, please refer to the applied generic or product family standards for edition information:

For dated basic standards, only the edition cited applies. For undated basic standards, the latest edition (including any amendments) applies.

1.1 Complementary Materials

All attachments are integral parts of this test report. This applies especially to the following appendix:

Appendix 1: Test Result

Appendix 2: List of Test and Measurement Equipment.

2 Test Sites

2.1 Test Facilities

TÜV Rheinland (Guangdong) Ltd. EMC Laboratory

No.102, 1F of Southwest and No.205, 2F of West Warehouse Building, No.767 Tianyuan Road, Tianhe District, Guangzhou, Guangdong, P.R.China

2.2 List of Test and Measurement Instruments

Table 1: List of Test and Measurement Equipment

Refer to attached Appendix 2

3 General Product Information

The submitted samples WS-EUK03 and WS-EUK04 are Smart Wall Switch with ZigBee wireless control for household lamp control used.

Model WS-EUK03 and WS-EUK04 have the same electronic designed and wireless module except for the structure. WS-EUK04 has two control loops; WS-EUK03 has one control loop.

Based on above information, full tests were performed on model WS-EUK04.

3.1 Product Function and Intended Use

Refer to the Technical Documentation and User Manual for further details.

3.2 Ratings and System Details

Type designation	:	WS-EUK03, WS-EUK04
Rated input	:	AC100-250V, 50/60Hz, Max. 8A (Resistive Load)
Protection class	:	II
Port	:	AC Mains input, AC load port
Cable type	:	Unshielded

3.3 Independent Operation Modes

The basic operation modes are:

- A. On, maximum disturbance with maximum load
- B. On-Off-On, 24 times.
- C. Off(standby mode)

Refer to User Manual for further details.

3.4 Noise Generating and Noise Suppressing Parts

Refer to Technical Documentation for further details.

3.5 Submitted Documents

Circuit Diagram
PCB Layout
Rating Label
User Manual
Difference Declaration

4 Test Set-up and Operation Modes

4.1 Principle of Configuration Selection

Emission: The equipment under test (EUT) was configured to measure its highest possible radiation level. The test modes were adapted accordingly in reference to the instructions for use.

Immunity: The equipment under test (EUT) was configured to have its highest possible susceptibility against the tested phenomena. The test modes were adapted accordingly in reference to the instructions for use.

4.2 Test Operation and Test Software

Refer to test set-up in chapter 5 and chapter 6.

4.3 Special Accessories and Auxiliary Equipment

None.

4.4 Countermeasures to achieve EMC Compliance

No additional countermeasures to the submitted test sample(s) were employed to achieve compliance.

5 Test Results EMISSION

5.1 Emission in the Frequency Range up to 30 MHz

5.1.1 Harmonics Current Emission on AC Mains

RESULT: Pass

Test Specification

Basic standard	:	EN IEC 61000-3-2:2019
Measurement equipment requirement	:	IEC 61000-4-7
Measured harmonics	:	1 – 40
Equipment class	:	C
Limits	:	Clause 7.1 and 7.3

Test Setup

Date of testing	:	Refer to appendix 1
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Artificial hand	:	N/A
Test configuration	:	Table-top
Temperature	:	Refer to appendix 1
Humidity	:	Refer to appendix 1
Air pressure	:	Refer to appendix 1

Photograph 1: Set-up for Harmonic Current Emission on AC Mains



For test results, please refer to the attached appendix 1.

5.1.2 Voltage Changes, Voltage Fluctuations and Flicker

RESULT: Pass

Test Specification

Basic standard	:	EN 61000-3-3: 2013+A1
Measurement equipment requirement	:	IEC 61000-4-15
Limits	:	EN 61000-3-3: 2013+A1, Clause 5

Test Setup

Date of testing	:	2020.08.05
Input voltage	:	AC 230V, 50Hz
Operation mode	:	B
Artificial hand	:	N/A
Test configuration	:	Table-top
Temperature	:	23.6°C
Humidity	:	63%
Air pressure	:	101kPa

Prüfbericht - Nr.: CN21U8UU 001
Test Report No.Seite 12 von 29
Page 12 of 29**Photograph 2: Set-up for Voltage Changes, Voltage Fluctuations and Flicker****Test Result**

Parameter	Pst	Plt	d(t) ms	dc %	dmax %
Limit	1	0.65	200	3	4
WS-EUK04	/	/	0	1.34	1.58

5.1.3 Terminal Continuous Disturbance Voltage

RESULT:**Pass****Test Specification**

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12, clause 26.2.2
Test procedure	:	EN 55015:2013+A1,clause 8
Port	:	Mains, Load Terminal
Frequency range of Mains	:	9kHz-30MHz
Test site	:	Shielded Room
Limits	:	EN 55015:2013+A1,Clause 4.3 Table 2a, 2b

Test Setup

Date of testing	:	Refer to appendix 1
Input voltage	:	AC 100V, 60Hz and AC 250V, 50Hz
Operation mode	:	A
Test Ports	:	AC Mains, Load terminal
Artificial hand	:	N/A
Test configuration	:	Table-top
Temperature	:	Refer to appendix 1
Humidity	:	Refer to appendix 1
Air pressure	:	Refer to appendix 1

Photograph 3: Set-up for Mains Terminal Disturbance Voltage



Test Result

Measurement uncertainty: 1.98 dB($k=2$, $\sigma = 95\%$)

If the result of the measurement with the Quasi Peak detector is below the Average limit, the measurement with Average Detector has been omitted.

Disturbances other than those mentioned are small or not detectable.

6 Test Results IMMUNITY

6.1 Classification of Apparatus

According to EN 60669-2-1: 2004+A1+A12, the EUT shall be tested in accordance with table 104, 105, 106 & 107, and comply with following performance criterion:

Power-frequency Magnetic Field	Criterion A
Radio-frequency Electromagnetic Field Amplitude Modulated (RS)	Criterion A
Radio-frequency Common Mode / Conducted Susceptibility (CS)	Criterion A
Electrical Fast Transients (EFT)	Criterion B
Surges	Criterion B
Electrostatic Discharge (ESD)	Criterion B
Voltage Dips and Interruptions	Criterion B

6.2 Continuous Disturbances

6.2.1 Power-frequency Magnetic Field

RESULT:

N/A

Test Specification

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-8
Frequency	:	50Hz or 60Hz
Magnetic field strength	:	3 A/m
Performance criterion	:	A

The EUT does not contain devices susceptible to magnetic fields, such as CRT monitors, Hall elements, electrodynamic microphones, magnetic field sensors, etc. Therefore, this test is not applicable and skipped.

*) EN 60669-2-1, clause 26.1.7: "This test is applicable only to electronic switches containing devices susceptible to magnetic fields, for example Hall elements, electrodynamic microphones, etc."

6.2.2 Radio-frequency Common Mode / Conducted Susceptibility (CS)

RESULT: Pass

Test Specification

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-6
Characteristics of test generator	:	
Output impedance	:	50 Ω
Harmonics and distortion	:	Any spurious spectral line at least 15 dB below the carrier level
Amplitude modulation	:	80 % ± 5 % in depth, 1 kHz ± 10 % sine wave
Frequency bandwidth	:	150 kHz to 80 MHz
Frequency step	:	1% with 1 s dwell time
Performance criterion	:	A

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Signal lines and control lines	:	N/A
Input and output dc power ports	:	N/A
Input and output ac power ports	:	3V (rms)
Temperature	:	24 °C
Humidity	:	58 %
Air pressure	:	101 kPA

Photograph 4: Set-up for Radio-frequency Common Mode / Conducted Susceptibility (CS)

Test Result
Table 2: Immunity against Radio-frequency Common Mode / Conducted Susceptibility (CS)

Coupling point	Application	Level (V(r.m.s))	Remark
Power ports			
AC input port	CDN-M2	3(150KHz~80MHz)	Applied, *)
AC output port	EM clamp	3(150KHz~80MHz)	Applied, *)
Signal and control lines			
	Current Clamp	3	N/A
	EM clamp	3	N/A

*) Remark: No degradation was observed during and after the tests.

6.2.3 Radio-frequency Electromagnetic Field Susceptibility (RS)

RESULT:**Pass****Test Specification**

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-3
Test level	:	1/3/10 V/m(un-modulated)
Frequency range	:	80MHz-1000MHz, 1400MHz-2000MHz 2000MHz-2700MHz
Modulation	:	1 kHz sine-wave, 80% AM
Sweep mode	:	Automatic
Sweep step	:	1%
Dwell time	:	≥ 1 Sec
Performance criterion	:	A

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Ports	:	Enclosure
Temperature	:	24 °C
Humidity	:	58 %
Air pressure	:	101 kPA

Photograph 5: Set-up for Radio-frequency Electromagnetic Field Susceptibility

Test Result
Table 3: Immunity against Radio-frequency Electromagnetic Field Susceptibility (RS)

Field Polarization	Side of EUT	Frequency Band	Strength (unmodulated, r.m.s)	Result	Remarks
Horizontal Vertical	Left Right Front Rear	80-1000MHz/ 1400-200MHz	3 V/m	passed	see *) below

*) Remark: No degradation was observed during and after the tests.

6.3 Transient Disturbances

6.3.1 Electrical Fast Transients (EFT)

RESULT:**Pass****Test Specification**

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-4
Wave shape of pulse in 50 Ω load	:	
Rise time	:	5 ns ± 30 %
Duration	:	50 ns ± 30 %
Wave shape into 1 kΩ load	:	
Rise time	:	5 ns ± 30 %
Duration	:	50 ns with a tolerance of -15 ns to + 100 ns
Burst duration	:	15 ms ± 20 % at 5 kHz
Burst period	:	300 ms ± 20 %
Repetition frequency	:	5 kHz
Polarity	:	Positive and negative
Time of application	:	2 minutes
Performance criterion	:	B

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Signal and control ports	:	N/A
Input and output dc power ports	:	N/A
Input and output ac power ports	:	1 KV
Temperature	:	22 °C
Humidity	:	52 %
Air pressure	:	101 kPA

Photograph 6: Set-up for Electrical Fast Transient (EFT)

Test Result
Table 4: Immunity against Electrical Fast Transients (EFT)

Coupling point	Application	Level (kV)	Polarity	Remark
Power ports				
AC input port	Coupling network	1	+	Applied, *)
		1	-	Applied, *)
AC output port	Coupling clamp	0.5	+	Applied, *)
		0.5	-	Applied, *)
Signal lines				
	Coupling clamp	0.5	+	N/A
		0.5	-	N/A
Control lines				
	Coupling clamp	0.5	+	N/A
		0.5	-	N/A

*) Remark: No degradation was observed during and after the tests.

6.3.2 Surge

RESULT: Pass

Test Specification

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-5
Definitions of waveform parameters :		
Front time		1.2 µs ± 30 %
Time to half value		50 µs ± 20 %
Source impedance	:	
Power line symmetrical		2 Ω + 18 µF
Power line unsymmetrical		12 Ω + 9 µF
Polarity	:	Positive and negative
No. of surges / polarity /phase angle	:	5
Phase angles	:	0°, 90° and 270 °
Repetition rate	:	60 s
Performance criterion	:	C

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Temperature	:	24 °C
Humidity	:	53 %
Air pressure	:	101 kPa

Photograph 7: Set-up for Surge on AC Power Supply

Test Result
Table 5: Surge Immunity Tests Result

Coupling point	Application	Level (kV)	Polarity	Remark
AC power port	Between phase and neutral	0.5, 1.0	+	Applied, *)
		0.5, 1.0	-	Applied, *)
AC power port	Between phase and earth	N/A	+	N/A
		N/A	-	N/A
AC power port	Between neutral and earth	N/A	+	N/A
		N/A	-	N/A

*) Remark: No degradation was observed during and after the tests.

6.3.3 Electrostatic Discharges (ESD)

RESULT:**Pass****Test Specification**

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-2
Discharge impedance	:	330 Ω / 150 pF
No. of discharges	:	Contact discharge: ≥10 Air discharge: ≥10
Type of discharge	:	
Direct discharge	:	Air discharge, ±8kV Contact discharge, ±4kV
Indirect discharge	:	Contact discharge, ±4kV
Polarity	:	Positive and negative
Discharge location	:	See photo documentation of the test set-up All external locations accessible by hand Horizontal coupling plate (HCP) Vertical coupling plate (VCP)
Performance criterion	:	B

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Temperature	:	24 °C
Humidity	:	56 %
Air pressure	:	101 kPA

Photograph 8: Set-up for Electrostatic Discharge
⚡ Contact Discharge $\pm 4\text{kV}$
⚡ Air Discharge $\pm 8\text{kV}$

Test Result
Table 6: Electrostatic Discharge

Direct discharges			
Air discharges Discharge location	Air discharge voltage (kV)	Polarity	Remark
Refer to Photograph of ESD	8	\pm	Applied, *)
Enclosure	8	\pm	Applied, *)
Contact discharges Discharge location			
Contact discharge voltage (kV)	Polarity	Remark	
Refer to Photograph of ESD	4	\pm	N/A
Conductive parts	4	\pm	Applied, *)
Indirect discharges			
Contact discharges Discharge location	Contact discharge voltage (kV)	Polarity	Remark
VCP	4	\pm	Applied, *)
HCP	4	\pm	Applied, *)

*) Remark: No degradation was observed during and after the tests.

6.4 Power Supply Alteration

6.4.1 Voltage Dips and Interruptions

RESULT:**Pass****Test Specification**

Family standard	:	EN 60669-1:1999+A1+A2 EN 60669-2-1: 2004+A1+A12
Basic standard	:	IEC 61000-4-11
Test voltage generator characteristics for interruptions :		
Rise time	:	Between 1 µs and 5 µs
Fall time	:	Between 1 µs and 5 µs
Output impedance of test voltage generator	:	<(0.4 + j 0.25 Ω)
Phase angle	:	0°
Nominal mains voltage (Ut)	:	AC 230 V
Rated frequency	:	50Hz
No. of interruptions	:	3
No. of voltage dips	:	3
Interval	:	>10s
Performance criterion	:	B

Test Setup

Date of testing	:	2021.03.12
Input voltage	:	AC 230V, 50Hz
Operation mode	:	A
Temperature	:	22 °C
Humidity	:	53 %
Air pressure	:	101 kPa

Photograph 9: Set-up for Voltage Dips and Interruptions

Test Result
Table 7: Voltage Dip and Interruptions Immunity

Interruptions			
Test level (% Ut)	Duration (cycle)	No. of interruptions	Result
0	10	10	Applied, *)
Voltage dips			
Test level (% Ut)	Duration (cycle)	No. of voltage dips	Result
40	10	10	Applied, *)
70	10	10	Applied, *)

*) Remark: No degradation was observed during and after the tests.

7 List of Tables

Table 1: List of Test and Measurement Equipment.....	5
Table 2: Immunity against Radio-frequency Common Mode / Conducted Susceptibility (CS) ...	18
Table 3: Immunity against Radio-frequency Electromagnetic Field Susceptibility (RS)	20
Table 4: Immunity against Electrical Fast Transients (EFT)	22
Table 5: Surge Immunity Tests Result.....	24
Table 6: Electrostatic Discharge	26
Table 7: Voltage Dip and Interruptions Immunity	28

8 List of Photographs

Photograph 1: Set-up for Harmonic Current Emission on AC Mains	10
Photograph 2: Set-up for Voltage Changes, Voltage Fluctuations and Flicker	12
Photograph 3: Set-up for Mains Terminal Disturbance Voltage	14
Photograph 4: Set-up for Radio-frequency Common Mode / Conducted Susceptibility (CS)....	18
Photograph 5: Set-up for Radio-frequency Electromagnetic Field Susceptibility	20
Photograph 6: Set-up for Electrical Fast Transient (EFT)	22
Photograph 7: Set-up for Surge on AC Power Supply	24
Photograph 8: Set-up for Electrostatic Discharge	26
Photograph 9: Set-up for Voltage Dips and Interruptions	28

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 1 von 19**Page 1 of 19****EMC Test Record**

Receipt No.:170259209	Page: Of
Report No.:	
Is this test result compliant with the requirements in the test plan? <input checked="" type="checkbox"/> Yes / <input type="checkbox"/> No	

Emission	Disturbance in supply system	<input checked="" type="checkbox"/> EN/IEC 61000-3-2 <input type="checkbox"/> EN/IEC 61000-3-12	
Harmonics on AC Mains			
Test voltage / Freq.: AC 230V/50 Hz		Climatic conditions: 22 °C; 52 %RH;	
Test Site: TUV Rheinland (Guangdong) Ltd. EMC Lab			
Model: WS-EUK04		Equipment:	
Operation Mode: A		<input checked="" type="checkbox"/> DPA 500 <input checked="" type="checkbox"/> ACS 500	
Harmonics Tables see page :			
Note:			
Settings	General Data		
Voltage	Current	Power	Power Fact.

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 2 von 19*Page 2 of 19***Test Report**

Report Number :	230V Har
Test Standard :	IEC 61000-3-2 (Edition 5) Limits for harmonic current emissions (equipment input current < 16 A per phase)
Test Date :	3/12/2021 1:59:50 PM

Result

E.U.T. :	PASS	Source :	PASS
----------	------	----------	------

Measures & Analysis

Measure Window :	10 periods	Voltage Range :	500 V
Refresh Interval :	2 s	Current Range :	50 A
Sampling Rate :	6.4 kS/s		
Scaled Window :	Rectangular		
According :	IEC 61000-3-2 (Edition 5) Limits for harmonic current emissions (equipment input current < 16 A per phase)		
Observation Period :	Quasi-stationary		

Measure Results**Standard Specific Results for IEC 61000-3-2 (Edition 5)**

Standard Group:	Industry
Standard Name:	IEC 61000-3-2 (Edition 5) Limits for harmonic current emissions (equipment input current < 16 A per phase)
Device Under Test:	PASS
Power Source:	PASS
Connection Type:	L - N
Classification:	Class C (Rated power > 25 W)

Check Harmonics 2..40 [exception odd 21..39]

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 3 von 19**Page 3 of 19**

<i>First detected harmonic order > 150 %</i>							
Line 1:	None						
<i>Harmonics orders > 150 %</i>							
Line 1:	None						
<i>Harmonics orders with average > 100 %</i>							
Line 1:	None						
Check Odd Harmonics 21..39							
<i>First detected time window with partial > partial limits</i>							
	<i>time window (time)</i>	<i>measured value</i>	<i>limit</i>				
Line 1:	None		9.49 %				
<i>Maximal time window with partial > partial limits</i>							
	<i>time window (time)</i>	<i>measured value</i>	<i>limit</i>				
Line 1:	None		9.49 %				
<i>First detected harmonic order > 150 %</i>							
Line 1:	None						
<i>Harmonics orders > 150 %</i>							
Line 1:	None						
<i>Harmonics orders with average > 150 %</i>							
Line 1:	None						
Measured values							
<i>Fundamental Current</i>							
Line 1:	7.41 A						
<i>Active input Power</i>							
Line 1:	1705.608 W *						
<i>Circuit power factor</i>							
Line 1:	1 *						
<i>* Absolute value.</i>							
Current Test Result							
<i>Average and Maximum harmonic current results</i>							
<i>Hn</i>	<i>Average (100% / 150% *)</i>			<i>Maximum (150%)</i>			<i>Harmonic Result</i>
	<i>Ieff [%]</i>	<i>of Limit [%]</i>	<i>Limit [%]</i>	<i>Result</i>	<i>Ieff [%]</i>	<i>of Limit [%]</i>	
1	99.826			100.000			

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 4 von 19**Page 4 of 19**

2	0.032	1.617	2.000	n/a	0.038	1.265	3.000	n/a	n/a
3	0.061	0.203	30.000	n/a	0.084	0.186	45.000	n/a	n/a
4	0.044				0.048				
5	0.021	0.214	10.000	n/a	0.027	0.183	15.000	n/a	n/a
6	0.023				0.028				
7	0.025	0.358	7.000	n/a	0.028	0.270	10.500	n/a	n/a
8	0.026				0.029				
9	0.035	0.707	5.000	n/a	0.038	0.510	7.500	n/a	n/a
10	0.023				0.027				
11	0.040	1.325	3.000	n/a	0.043	0.959	4.500	n/a	n/a
12	0.020				0.023				
13	0.015	0.503	3.000	n/a	0.017	0.381	4.500	n/a	n/a
14	0.022				0.025				
15	0.018	0.598	3.000	n/a	0.020	0.451	4.500	n/a	n/a
16	0.020				0.023				
17	0.036	1.214	3.000	n/a	0.040	0.892	4.500	n/a	n/a
18	0.022				0.023				
19	0.049	1.639	3.000	n/a	0.052	1.165	4.500	n/a	n/a
20	0.019				0.021				
21	0.011	0.240	4.500	n/a	0.013	0.295	4.500	n/a	n/a
22	0.019				0.022				
23	0.015	0.327	4.500	n/a	0.018	0.396	4.500	n/a	n/a
24	0.014				0.016				
25	0.024	0.532	4.500	n/a	0.028	0.614	4.500	n/a	n/a
26	0.016				0.019				
27	0.035	0.768	4.500	n/a	0.040	0.894	4.500	n/a	n/a
28	0.014				0.017				
29	0.018	0.389	4.500	n/a	0.021	0.461	4.500	n/a	n/a
30	0.012				0.014				
31	0.013	0.293	4.500	n/a	0.016	0.359	4.500	n/a	n/a
32	0.011				0.013				
33	0.011	0.244	4.500	n/a	0.015	0.338	4.500	n/a	n/a
34	0.012				0.015				
35	0.027	0.594	4.500	n/a	0.032	0.709	4.500	n/a	n/a
36	0.011				0.013				
37	0.027	0.597	4.500	n/a	0.030	0.672	4.500	n/a	n/a
38	0.011				0.012				
39	0.017	0.377	4.500	n/a	0.021	0.474	4.500	n/a	n/a
40	0.012				0.014				

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 5 von 19*Page 5 of 19*

Note: Harmonic currents less than 0.6 % of the input current measured under the test conditions, or less than 5 mA, whichever is greater, are disregarded.

** Application of limits for average is 100% except for odd harmonics from 21 to 39, where 150% applies.*

Voltage Source Verification

Harmonic voltage results				
Hn	Ueff [V]	Ueff [%]	Limit [%]	Result
1	230.197	100.086		
2	0.052	0.023	0.200	PASS
3	0.080	0.035	0.900	PASS
4	0.028	0.012	0.200	PASS
5	0.061	0.026	0.400	PASS
6	0.023	0.010	0.200	PASS
7	0.038	0.016	0.300	PASS
8	0.020	0.009	0.200	PASS
9	0.075	0.032	0.200	PASS
10	0.011	0.005	0.200	PASS
11	0.059	0.026	0.100	PASS
12	0.012	0.005	0.100	PASS
13	0.029	0.013	0.100	PASS
14	0.018	0.008	0.100	PASS
15	0.044	0.019	0.100	PASS
16	0.015	0.006	0.100	PASS
17	0.072	0.031	0.100	PASS
18	0.015	0.007	0.100	PASS
19	0.087	0.038	0.100	PASS
20	0.013	0.005	0.100	PASS
21	0.051	0.022	0.100	PASS
22	0.011	0.005	0.100	PASS
23	0.021	0.009	0.100	PASS
24	0.012	0.005	0.100	PASS
25	0.064	0.028	0.100	PASS
26	0.015	0.007	0.100	PASS
27	0.077	0.034	0.100	PASS
28	0.014	0.006	0.100	PASS
29	0.059	0.025	0.100	PASS
30	0.013	0.006	0.100	PASS
31	0.028	0.012	0.100	PASS
32	0.014	0.006	0.100	PASS
33	0.038	0.017	0.100	PASS

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:

CN21U8UU 001

Test Report No.

Seite 6 von 19

Page 6 of 19

34	0.011	0.005	0.100	PASS
35	0.067	0.029	0.100	PASS
36	0.011	0.005	0.100	PASS
37	0.064	0.028	0.100	PASS
38	0.014	0.006	0.100	PASS
39	0.051	0.022	0.100	PASS
40	0.009	0.004	0.100	PASS

Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318


Prüfbericht - Nr.:

CN21U8UU 001

Test Report No.

Seite 7 von 19

Page 7 of 19



Tested by

Lisa Liu

Reviewed by

Jacky Chen

Date:

20210317

Date: 20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 8 von 19**Page 8 of 19**

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 20°C; 50%RH; 101 kPa.
 Test Voltage/ Freq.: AC 100 V/ 60 Hz
 Port / Line: Output line 2
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: ESH2-Z3 Voltage Probe
 Level Unit: dB μ V

Subrange	Detectors	IF Bandwidth	Step Size	Meas. Time	Receiver
150kHz - 30MHz	Peak; Average	9kHz	4.5kHz	10ms	ESCI



Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 9 von 19*Page 9 of 19*

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Corr. (dB)
1.266000	---	59.86	64.00	4.14	1000.0	9.000	30.1
1.266000	60.23	---	74.00	13.77	1000.0	9.000	30.1
1.510000	---	59.28	64.00	4.72	1000.0	9.000	30.1
1.510000	61.43	---	74.00	12.57	1000.0	9.000	30.1
1.542000	---	62.41	64.00	1.59	1000.0	9.000	30.1
1.542000	63.60	---	74.00	10.40	1000.0	9.000	30.1
1.602000	59.52	---	74.00	14.48	1000.0	9.000	30.1
1.602000	---	58.96	64.00	5.04	1000.0	9.000	30.1
5.910000	58.53	---	74.00	15.47	1000.0	9.000	30.3
5.910000	---	58.10	64.00	5.90	1000.0	9.000	30.3
6.702000	---	57.10	64.00	6.90	1000.0	9.000	30.3
6.702000	58.44	---	74.00	15.56	1000.0	9.000	30.3

Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 10 von 19

Page 10 of 19

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 20°C; 50%RH; 101 kPa.
 Test Voltage/ Freq.: AC 100 V/ 60 Hz
 Port / Line: Output line 2
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: ESH2-Z3 Voltage Probe
 Level Unit: dB μ V

Subrange 150kHz - 30MHz	Detectors Peak; Average	IF Bandwidth 9kHz	Step Size 4.5kHz	Meas. Time 10ms	Receiver ESCI
----------------------------	----------------------------	----------------------	---------------------	--------------------	------------------



Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 11 von 19**Page 11 of 19**

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Corr. (dB)
1.266000	---	59.86	64.00	4.14	1000.0	9.000	30.1
1.266000	60.24	---	74.00	13.76	1000.0	9.000	30.1
1.482000	57.86	---	74.00	16.14	1000.0	9.000	30.1
1.510000	---	59.16	64.00	4.84	1000.0	9.000	30.1
1.510000	61.36	---	74.00	12.64	1000.0	9.000	30.1
1.542000	---	62.31	64.00	1.69	1000.0	9.000	30.1
1.542000	63.54	---	74.00	10.46	1000.0	9.000	30.1
1.602000	---	58.90	64.00	5.10	1000.0	9.000	30.1
5.910000	58.49	---	74.00	15.51	1000.0	9.000	30.3
5.910000	---	58.08	64.00	5.92	1000.0	9.000	30.3
6.702000	---	57.14	64.00	6.86	1000.0	9.000	30.3
6.702000	58.40	---	74.00	15.60	1000.0	9.000	30.3

Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 12 von 19**Page 12 of 19**

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 21 °C; 50 %RH; 101 kPa.
 Test Voltage/ Freq.: AC 100 V/ 60 Hz
 Port / Line: AC Mains(L1+N)
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: 1phase LISN ENV216 to ESCI 3
 Level Unit: dB μ V

Subrange	Detectors	IF Bandwidth	Step Size	Meas. Time	Receiver
9kHz - 150kHz	Peak	200Hz	100Hz	50ms	ESCI 3
150kHz - 30MHz	Peak; Average	9kHz	4.5kHz	10ms	ESCI 3



Tested by:

Lisa Lin

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 13 von 19**Page 13 of 19**

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Line	Filter	Corr. (dB)
0.694500	---	32.15	46.00	13.85	1000.0	9.000	N	OFF	9.7
0.721500	---	31.91	46.00	14.09	1000.0	9.000	N	OFF	9.7
0.780000	36.38	---	56.00	19.62	1000.0	9.000	N	OFF	9.7
0.856500	36.13	---	56.00	19.87	1000.0	9.000	L1	OFF	9.7
0.861000	---	32.42	46.00	13.58	1000.0	9.000	L1	OFF	9.7
0.910500	36.94	---	56.00	19.06	1000.0	9.000	L1	OFF	9.7
0.915000	---	33.16	46.00	12.84	1000.0	9.000	L1	OFF	9.7
0.969000	36.41	---	56.00	19.59	1000.0	9.000	L1	OFF	9.7
0.969000	---	32.04	46.00	13.96	1000.0	9.000	N	OFF	9.7
1.032000	---	31.64	46.00	14.36	1000.0	9.000	N	OFF	9.7
1.189500	34.72	---	56.00	21.28	1000.0	9.000	N	OFF	9.7
2.958000	33.47	---	56.00	22.53	1000.0	9.000	N	OFF	9.8

Tested by:

Lisa Lin

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 14 von 19

Page 14 of 19

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 20°C; 50%RH; 101 kPa.
 Test Voltage/ Freq.: AC 250 V/ 50 Hz
 Port / Line: Output line 2
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: ESH2-Z3 Voltage Probe
 Level Unit: dB μ V

Subrange 150kHz - 30MHz	Detectors Peak; Average	IF Bandwidth 9kHz	Step Size 4.5kHz	Meas. Time 10ms	Receiver ESCI
----------------------------	----------------------------	----------------------	---------------------	--------------------	------------------



Tested by:

Lisa Lin

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 15 von 19**Page 15 of 19**

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Corr. (dB)
1.266000	---	59.87	64.00	4.13	1000.0	9.000	30.1
1.266000	60.34	---	74.00	13.66	1000.0	9.000	30.1
1.510000	---	60.94	64.00	3.06	1000.0	9.000	30.1
1.510000	61.93	---	74.00	12.07	1000.0	9.000	30.1
1.542000	---	63.69	64.00	0.31	1000.0	9.000	30.1
1.542000	63.94	---	74.00	10.06	1000.0	9.000	30.1
1.602000	60.01	---	74.00	13.99	1000.0	9.000	30.1
1.602000	---	59.88	64.00	4.12	1000.0	9.000	30.1
5.910000	58.83	---	74.00	15.17	1000.0	9.000	30.3
5.910000	---	58.23	64.00	5.77	1000.0	9.000	30.3
6.702000	58.34	---	74.00	15.66	1000.0	9.000	30.3
18.242000	---	58.13	64.00	5.87	1000.0	9.000	30.4

Tested by:
Lisa LiuReviewed by:
Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 16 von 19

Page 16 of 19

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 20°C; 50%RH; 101 kPa.
 Test Voltage/ Freq.: AC 250 V/ 50 Hz
 Port / Line: Output line 2
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: ESH2-Z3 Voltage Probe
 Level Unit: dB μ V

Subrange 150kHz - 30MHz	Detectors Peak; Average	IF Bandwidth 9kHz	Step Size 4.5kHz	Meas. Time 10ms	Receiver ESCI
----------------------------	----------------------------	----------------------	---------------------	--------------------	------------------



Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 17 von 19**Page 17 of 19**

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Line	Corr. (dB)
1.266000	---	59.89	64.00	4.11	1000.0	9.000	Single Line	30.1
1.266000	60.34	---	74.00	13.66	1000.0	9.000	Single Line	30.1
1.482000	58.60	---	74.00	15.40	1000.0	9.000	Single Line	30.1
1.510000	---	60.93	64.00	3.07	1000.0	9.000	Single Line	30.1
1.510000	61.93	---	74.00	12.07	1000.0	9.000	Single Line	30.1
1.542000	---	63.69	64.00	0.31	1000.0	9.000	Single Line	30.1
1.542000	63.91	---	74.00	10.09	1000.0	9.000	Single Line	30.1
1.602000	---	59.91	64.00	4.09	1000.0	9.000	Single Line	30.1
1.602000	60.01	---	74.00	13.99	1000.0	9.000	Single Line	30.1
5.910000	---	58.16	64.00	5.84	1000.0	9.000	Single Line	30.3
5.910000	58.83	---	74.00	15.17	1000.0	9.000	Single Line	30.3
18.242000	---	58.50	64.00	5.50	1000.0	9.000	Single Line	30.4

Tested by:

Lisa Liu

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 18 von 19**Page 18 of 19**

TUV Rheinland (Guangdong) Ltd.


EMC Test Service Hotline: +86-20-28391188

EMC Test Record (EMISSION)**Test Information**

Manufacturer: Lumi
 Test Item: Smart Wall Switch
 Identification: WS-EUK04
 Test Standard: EN55015
 Test Detail: Conducted Emission
 Operation Mode: A
 Climate Condition: 21 °C; 50 %RH; 101 kPa.
 Test Voltage/ Freq.: AC 250 V/ 50 Hz
 Port / Line: AC Mains(L1+N)
 Receipt No.: 170259209
 Report No.: /
 Result: Pass
 Comment: /

Hardware Setup: 1phase LISN ENV216 to ESCI 3
 Level Unit: dB μ V

Subrange	Detectors	IF Bandwidth	Step Size	Meas. Time	Receiver
9kHz - 150kHz	Peak	200Hz	100Hz	50ms	ESCI 3
150kHz - 30MHz	Peak; Average	9kHz	4.5kHz	10ms	ESCI 3



Tested by:

Lisa Lin

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:**CN21U8UU 001**

Test Report No.

Seite 19 von 19**Page 19 of 19**

TUV Rheinland (Guangdong) Ltd.

EMC Test Service Hotline: +86-20-28391188

Final_Result

Frequency (MHz)	QuasiPeak (dB μ V)	CAverage (dB μ V)	Limit (dB μ V)	Margin (dB)	Meas. Time (ms)	Bandwidth (kHz)	Line	Filter	Corr. (dB)
0.505500	---	28.56	46.00	17.44	1000.0	9.000	N	OFF	9.6
0.505500	31.25	---	56.00	24.75	1000.0	9.000	L1	OFF	9.6
0.937500	35.48	---	56.00	20.52	1000.0	9.000	L1	OFF	9.7
0.987000	---	30.97	46.00	15.03	1000.0	9.000	L1	OFF	9.7
1.176000	---	31.88	46.00	14.12	1000.0	9.000	N	OFF	9.7
1.194000	34.72	---	56.00	21.28	1000.0	9.000	N	OFF	9.7
3.507000	---	30.59	46.00	15.41	1000.0	9.000	N	OFF	9.8
3.556500	33.77	---	56.00	22.23	1000.0	9.000	N	OFF	9.8
5.536500	31.53	---	60.00	28.47	1000.0	9.000	L1	OFF	9.9
5.833500	---	28.54	50.00	21.46	1000.0	9.000	L1	OFF	9.9
5.941500	---	28.32	50.00	21.68	1000.0	9.000	N	OFF	9.9
5.941500	31.54	---	60.00	28.46	1000.0	9.000	N	OFF	9.9

Tested by:

Lisa Lin

Reviewed by:

Jacky Chen

20210317

20210318

Prüfbericht - Nr.:

Test Report No.

CN21U8UU 001

Seite 1 von 2

Page 1 of 2

**Table 1: List of Test and Measurement Equipment (TÜV Rheinland (Guangdong) Ltd.
EMC Laboratory)**

Equipment	Manufacturer	Model No.	Serial No.	Cal Until
Disturbance Voltage				
EMI Test Receiver	Rohde&Schwarz	ESCI 3	100314	2022-03-15
Two-Line V-Network	Rohde&Schwarz	ENV216	100195	2021-05-25
EMI Test Receiver	Rohde&Schwarz	ESR7	102110	2022-04-09
Artificial Mains Network	AFJ	LT32C/10	32031810253	2021-07-30
Impedance Stabilization Network	TESTQ	ISN T8	51991	2021-07-29
Harmonics & Flicker				
Harmonic and Flicker Analyzer	EM TEST	DPA 500	0304-01	2021-04-20
AC Source	EM TEST	ACS 500	0304-01	2021-04-20
Radiated Susceptibility				
Signal Generator	Rohde&Schwarz	SMB100A	115613	2021-04-08
Power Meter	Rohde&Schwarz	NRX	100863	2021-04-08
Average Power Sensor	Rohde&Schwarz	NRP6A	101980	2021-04-08
Average Power Sensor	Rohde & Schwarz	NRP6A	101981	2021-04-08
Antenna	Amplifier Research	AT1080	0320070	2021-04-12
RF 1-6GHz Amplifier	Milmega	AS0860B-100-100	1085687	2021-03-15
Broad-band Horn Antenna	BBHA 9120 J	Rohde & Schwarz	00176	2021-04-12
Conducted Susceptibility(150 kHz-230 MHz)				
Continuous Wave Simulator	EM TEST	CWS500 C	0404-04	2022-03-15
EM Clamp	Luthi	EM101	35697	2022-03-15
Test system for conducted and radiated immunity	TESEQ	NSG4070C-80	54285	2021-08-30
6dB Attenuator	TESEQ	ATN6150	19042601	2021-07-29
Electrical Fast Transient(EFT)				
Ultra Compact Simulator	EM TEST	UCS 500-M4	V0707102252	2022-03-15
EFT Test Coupling Clamp	TESEQ	CDN 3425	1916	2022-03-15

Prüfbericht - Nr.:

Test Report No.

CN21U8UU 001

Seite 2 von 2

Page 2 of 2

Equipment	Manufacturer	Model No.	Serial No.	Cal Until
Surge & Voltage dips and Interruption				
Ultra Compact Simulator	EM TEST	UCS 500-M4	V0707102252	2022-03-15
Motorised Variac	EM TEST	MV 2616	V0707102253	2022-03-15
Electrostatic Discharge				
ESD Gun	TESEQ	NSG 437	615	2021-07-02